

obliczRobot

TABELA ROBÓT ZIEMNYCH UL. BOLESŁAWA CHROBREGO						
PIKIETAŻ NADMIAR(*)	POWIERZCHNIE [m2] NASYP BILANS	WYKOP	ODLEGŁOŚĆ [m]	OBJĘTOŚCI [m3] NASYP	WYKOP	ZUŻYCIE NA MIEJSCU
0,00	0,00	10,25				
	0,00		12,50	2,37	78,25	2,37
75,88						
12,50	0,38	2,27				
	75,88		12,50	3,27	31,97	3,27
28,70						
25,00	0,14	2,84				
	104,58		12,50	2,01	36,85	2,01
34,84						
37,50	0,18	3,06				
	139,42		12,50	2,93	36,88	2,93
33,95						
50,00	0,29	2,85				
	173,37		12,50	5,31	32,85	5,31
27,55						
62,50	0,56	2,41				
	200,92		12,50	6,07	30,77	6,07
24,70						
75,00	0,41	2,51				
	225,62		12,50	3,84	33,46	3,84
29,62						
87,50	0,20	2,84				
	255,24		12,50	3,84	30,81	3,84
26,97						
100,00	0,41	2,09				
	282,21		12,50	10,18	25,88	10,18
15,70						
112,50	1,21	2,05				
	297,91		12,50	12,58	22,71	12,58
10,13						
125,00	0,80	1,58				
	308,04		12,50	6,72	23,69	6,72
16,98						
137,50	0,28	2,21				
	325,02		12,50	1,86	32,91	1,86
31,05						
150,00	0,02	3,06				
	356,07		12,50	0,58	40,77	0,58
40,19						
162,50	0,07	3,47				
	396,27		12,50	0,45	44,56	0,45
44,11						
175,00	0,00	3,66				

				obliczRobot			
440,37				12,50	0,00	48,07	0,00
48,07							
187,50	0,00	4,03					
488,45				12,50	3,46	41,79	3,46
38,33							
200,00	0,55	2,66					
526,78				12,50	10,02	27,49	10,02
17,48							
212,50	1,05	1,74					
544,25				12,50	7,49	41,28	7,49
33,79							
225,00	0,15	4,86					
578,04				12,50	1,77	63,21	1,77
61,43							
237,50	0,13	5,25					
639,47				12,50	1,40	61,03	1,40
59,63							
250,00	0,09	4,51					
699,10				12,50	2,42	54,64	2,42
52,22							
262,50	0,30	4,23					
751,32				12,50	4,29	42,99	4,29
38,70							
275,00	0,39	2,65					
790,02				12,50	2,64	35,61	2,64
32,97							
287,50	0,03	3,05					
822,99				12,50	0,74	36,15	0,74
35,41							
300,00	0,09	2,73					
858,39				12,50	0,58	34,70	0,58
34,12							
312,50	0,01	2,82					
892,51				12,50	0,05	42,64	0,05
42,59							
325,00	0,00	4,00					
935,10				12,50	0,01	49,90	0,01
49,89							
337,50	0,00	3,98					
984,99				12,50	4,63	39,18	4,63
34,55							
350,00	0,74	2,29					
1019,54				12,50	24,65	26,98	24,65
2,33							
362,50	3,20	2,03					
1021,88				12,50	40,49	16,01	16,01
-24,48							
375,00	3,27	0,53					
997,40				12,50	42,15	6,37	6,37
-35,78							
387,50	3,47	0,49					
961,62				12,50	39,97	8,45	8,45
-31,53							

				obliczRobot			
400,00	2,92	0,87					
930,09				12,50	25,14	17,72	17,72
-7,42							
412,50	1,10	1,97					
922,67				12,50	12,08	28,16	12,08
16,08							
425,00	0,84	2,54					
938,76				12,50	5,43	48,39	5,43
42,96							
437,50	0,03	5,21					
981,71				12,50	0,21	58,88	0,21
58,67							
450,00	0,00	4,22					
1040,38				12,50	0,15	47,22	0,15
47,07							
462,50	0,02	3,34					
1087,45				12,50	1,06	40,23	1,06
39,17							
475,00	0,15	3,10					
1126,62				15,00	3,56	42,97	3,56
39,42							
490,00	0,33	2,63					
1166,04							
RAZEM				296,38	1462,42	197,18	
Nadmiar WYKOP 1166,04m3							

(\*) - wartości ujemne NASYP, dodatnie WYKOP